

Summary of Modifications/Changes in this Update

This Summary of Changes is for information only.
It is not a part of the referenced document, and should not be used for project documentation.

U.S. Department of Veterans Affairs ♦ Office of Construction & Facilities Management

DATE OF THIS VERSION:

March 1, 2018

TITLE OF DOCUMENT:

Electric Traction Elevator, 142100

DATE OF VERSION BEING SUPERSEDED (old):

September 1, 2017

DESCRIPTION OF DOCUMENT (previous title, number, other identifying data):

Electric Traction Elevator, 142100

SUMMARY OF CHANGES IN THIS VERSION:

3.6 PRE-TESTS AND TESTS

- A. Pre-test the dumbwaiter and related equipment in the presence of the Resident Engineer or his authorized representative for proper operation before requesting final inspection. Conduct final inspection at other than normal working hours, if required by Resident Engineer.
 1. Contracting Officer shall obtain the services of a third party QEI Certified Elevator Inspector. The QEI must utilize an Elevator Acceptance Inspection Form to record the results of inspection and all testing and to identify safety code and contract deficiencies. Specific values must be provided for all tests required by ASME A17.1, ASME A17.2, and contract documents. Upon completion of inspection and testing, the QEI must sign a copy of the completed form and provide to the Contracting Officer. Within 2 weeks of the inspection, the QEI must also prepare a formal inspection report, including all test results and deficiencies. Upon successful

completion of inspection and testing, the QEI will complete, sign, and provide a certificate of compliance with ASME A17.1.